



Facilities & Construction Management Notice of Construction Activity Cogeneration Plant Upgrade

Description of Activity:**Ductbank Across Washington Place****Notice Date:****05-13-09**

The Office of Facilities and Construction Management is undertaking the upgrade and expansion of the NYU Cogeneration Plant. This work is required to install conduits from the 715 Broadway to 2 Washington Place.

Description of Construction Activity:

- A trench will be excavated across Washington Place between Broadway and Mercer Street. The work entails saw cutting and chopping to remove the pavement and excavating a trench. Holes for conduit sleeves will be core drilled into both buildings. Conduits are then installed in the trench and encased in concrete. The holes into the buildings are water sealed. The trench is then backfilled and the street surface restored to its original condition.
- The street will remain open to traffic at all times as the work will occur on only half the street at a time. The trench will be plated over after working hours and cordoned off during working hours.

Schedule:

- Work is scheduled to begin the week of May 18th and will be completed by the end of July, 2009. Contractor's hours are Monday thru Friday, 7AM to 4PM.

Disruptions:

- Noise - There will be noise during the saw-cutting and chopping of the trench.
- Dust - Water will be used to minimize dust during saw-cutting and excavation.
- Traffic - One lane of traffic will remain open at all times. Pedestrian traffic will be rerouted as needed.
- Parking - Parking will be eliminated near area of work on Washington Place.

Contact Information: Contact NYU Facilities & Construction Management Client Services Desk @ 212 998-1001 or via email at fcm.helpdesk@nyu.edu with any questions or concerns.