



**Facilities & Construction Management
Notice of Construction Activity
Cogeneration Plant Upgrade**

Description of Activity:

Ductbank Across LaGuardia Place

Notice Date: 02-16-09

The Office of Facilities and Construction Management is undertaking the upgrade and expansion of the NYU Cogeneration Plant. This work is required to install conduits from Bobst Library to Kimmel Student Center.

Description of Construction Activity:

- A trench will be excavated across LaGuardia Place just north of West 3rd Street. The work entails saw cutting and chopping to remove the pavement and excavating a trench from Bobst to Kimmel. Conduits are then installed in the trench and encased in concrete, and holes for conduit sleeves will be cored in both buildings. The trench is then backfilled and the street surface restored to its original condition.
- The street will remain open to traffic at all times as the work will occur on only half the street at a time. The trench will be plated over after working hours and cordoned off during working hours.

Schedule:

Work is scheduled to begin the week of February 16th, 2009 and will be completed by the end of March. Contractor's hours are Monday thru Friday, 7AM to 4PM. The schedule of work is as follows:

- saw cutting and chopping of trench
- trench excavation
- electrical ductbank installation
- core drillings into buildings
- backfill and surface restoration

Disruptions:

- Noise - There will be noise during the saw-cutting and chopping of the trench.
- Dust - Water will be used to minimize dust during saw-cutting and excavation.
- Traffic - One lane of traffic will remain open in both directions at all times. Pedestrian traffic will be rerouted as needed.
- Parking - Parking will be eliminated near area of work on LaGuardia Place.

Contact Information: Contact NYU Facilities & Construction Management Client Services Desk @ 212 998-1001 or via email at fcm.helpdesk@nyu.edu with any questions or concerns.